



Project: REPAIR AND REHABILITATION OF MULTI-PURPOSE COURT
Location: SLSU-MAIN, SOGOD CAMPUS, SOGOD, SOUTHERN LEYTE
Subject: SCOPE OF WORK/ MATERIAL SPECIFICATION/ WORKMANSHIP

The Contractor shall furnish labor, tools, equipment, PPE, and supervision to perform satisfactorily all the required works for the project. The work shall include but is not limited to mobilization, demobilization, excavation, masonry works, plastering, backfilling/compaction, construction of temporary facilities, and housekeeping.

A. MATERIAL SPECIFICATIONS

A.01 ROOFING WORKS

Trusses: Fully weld
C-Purlins: 50mm x 100mm x 1.5mm
Roof Sheet: Ga.#24 ordinary corrugated pre-painted roof sheets, Blue color
Ceiling Joist: Metal furring (double)

A.02 DOORS AND WINDOWS

Hidden framed curtain wall with awning window

A.03 WIND BORNE DEBRIS PROTECTION

Tubular Steel: 1.5mmthk Rectangular Tubular Steel
Flat Bar: 4"x1/4" Flat Bar
Anchor Bolts: 16mmØ x130mm Chemical Anchor Bolts (Stainless Steel)

A.04 STEEL WORKS

Angular Bar: 1 1/2"x1 1/2"x1/4" Angular Bar
Flat Bar: 4" x 1/4" Flat Bar
Anchor Bolts: 16mmØ x130mm Chemical Anchor Bolts (Stainless Steel)

A.05 PAINTING WORKS

Exterior Painting: Pressure clean and remove oil, grease and loose foreign matter which causes neither undue damage to the substrate nor damage to, or contamination of the surroundings or the paint system to be applied

B. WORKMANSHIP

B.01 Plastering works

- Minimum thickness is 1/2". Mortar mix must be put in place within 2 hours after water has been added. Follow the mixture specified in A.6 above. All plaster must be cement finish. Finish plaster must be water cured for at least three (3) days.

B.02 Formworks

- Coco lumber will be allowed for use provided its normal strength has not deteriorated. Installed forms must be sturdy, stiff durable, and with true/correct alignment & elevation; all to the satisfaction of Project's TWG. Deteriorated and/or misaligned forms will be dismantled and replace without cost to Project

B.03 Housekeeping

- Cleanliness and orderliness within the worksite is a must to enhance overall safety for the whole project.

B.04 Others

- Contractor's workers must always abide by Project's and School's safety and security rules and regulations. Violating workers will not be allowed to work and will be blacklisted. Details of these rules and regulations will be discussed during the kick-off meeting. List of workers and equipment must be submitted (w/ serial number) during the kick-off meeting.

Prepared by:

Sgd.
ENGR. RYAN A. MACUTO
Engineer II

Recommending Approval:

Sgd.
MABEL R. CALVA, MPA
VP-Admin and Finance

Approved by:

Sgd.
PROSE IVY G. YEPES, Ed.D.
University President